TC ARCHITECTS
430 GRANT STREET
AKRON, OH 44311

ADDENDUM NO. 02

September 28, 2026

To the Plans and Specifications for:

Trumbull Metropolitan Housing Authority
Site and Underground Utilities
TC Project No.: 2261004

TO ALL BIDDERS:

This Addendum supplements and amends the original Plans and Specifications and shall be taken into account in preparing proposals and shall become a part of the Contract Documents.

GENERAL CLARIFICATIONS AND INFORMATION

1. None at this time.

BID RFIs

1. On sheet C500 there is a detail for asphalt - 6" 304 stone, 3" 301 asphalt and 1" 404 LVT surface. The prints are pointing out full depth and then just repair. What is the full depth and what is the repair? Full depth I am assuming is the 4" what is the depth/detail of just the repair?
   Response: Areas noted as full depth asphalt replacement represent locations where an asphalt surface did not exist before and is being added. Areas noted as asphalt repair represents locations where an asphalt surface existed before, is being removed to complete the Work and is reinstalled to bring the area back to the condition it was prior to the start of the Work. Each instance will feature full depth asphalt installation and is represented on detail 3/C500.

2. Will a cost estimate be available?
   Response: The cost estimate for this project will not be released.

3. The city says that we could use existing sewer taps, is that ok?
   Response: Yes.

4. Are we replacing any existing water boxes?
   Response: No, water boxes are not anticipated to be replaced. However, should contractor damage them upon line installation, they shall be replaced at no additional cost to the Owner.

5. Do the bollards have to be reinstalled at Highland Terrace?
   Response: Any portion of the existing site that is removed to perform the Work shall be restored to its previous condition following completion of work.

6. Is 304 and 57 blast furnace stone ok to use?
   Response: No, this material is not an approved ODOT material in the use of pipe bedding or structural backfill. All material shall be submitted to engineer for review and approval prior to purchase and installation.

CHANGES TO SPECIFICATIONS SECTION

1. None at this time.

CHANGES TO DRAWINGS

1. None at this time.

Attachments: None.

END OF ADDENDUM 02